



15-147-20152-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1972  
CONSERVATION DIVISION  
Wichita, Kansas  
4-21-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Lahar of B & B Drlg. has this  
date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Leland R. Baird

Complete Address: First National Bank Logan, Kansas

Lease Name: Steel Trust Well No. 1

Location: NW NE NE Sec. 27 Twp. 5 Rge. (E)(W) 20

County: Phillips Total Depth 3654' Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Lahar was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey  
Conservation Division Agent