



15-147-19112-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1971
CONSERVATION DIVISION
Wichita, Kansas

6-30-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Shirer Oil Company,

Complete Address: Box #118, Hoisington, Kansas.

Lease Name: Steele Well No. 1

Location: SW-SW-NE Sec. 27 Twp. 5 Rge. (E)(W) 20

County: Phillips Total Depth Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

215'--8 5/8" Surface casing, cement circulated with 160 Sx.

3570'--5 1/2" Production casing cemented on bottom with 100 Sx. No Plug Back. Top perforations from 3556' to 3560'.

Sand hole back to 3525' and set 5 Sx. cement with Dump Bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 165 Sx. cement, staged.

Very truly yours,

Conservation Division Agent