



15-147-20160-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1973
CONSERVATION DIVISION
Wichita, Kansas
1-2-73

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Flax of Abercrombie Drlg. has this

date requested permission to plug the following described well:

Mr. Flax guarantees payment of the plugging fee.

Operator's full Name: Leland R. Baird

Complete Address: First National Bank, Logan, Ks.

Lease Name: Baird 2 NW SW Well No. 1

Location: C N/2 NW SW Sec. 11 Twp. 5 Rge. (E)(W) 20

County: Phillips Total Depth 3529' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Flax was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace

70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo P. Massey
Conservation Division Agent