



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1963

8-28-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Albert Schiffner of Forbes Casing Pulling Inc., has this

date requested permission to plug the following described well:

D & D Drilling Co, Inc.,

Mr. Schiffner guarantees payment of the plugging fee.

Operator's full Name: D & D Drilling Company, Inc.,

Complete Address: 308 Schweiter Bldg., Wichita, Kansas.

Lease Name: Williams Well No. 1

Location: CSE-SW Sec. 21 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3681 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schiffner was instructed to plug the well as follows:

240' -- 8 5/8" surface pipe, cement circulated. 3678' -- 5 1/2" cemented with 50 Sx.

Sand well back to 3670' and set 5 Sx cement with dump bailer.

Pull 5 1/2" to 550' and circulate heavy gel mud and displace 20 Sx

cement thru 5 1/2". Pull 5 1/2" to 230' and displace 20 Sx cement thru 5 1/2".

Pull 5 1/2" to 35', set plug and 10 Sx cement to bottom of cellar.

Very truly yours,

W. A. Nichols
Conservation Division Agent