



15-137-00290-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1970
CONSERVATION DIVISION
Wichita, Kansas

8-17-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Parsons of D. G. Hansen Trust has this

date requested permission to plug the following described well:

Mr. Parsons guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen Trust,

Complete Address: Box #187, Logan, Kansas.

Lease Name: Noone Well No. 2

Location: SW-NW-NW Sec. 18 Twp. 5 Rge. (E)(W) 21

County: Norton Total Depth 3540 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Parsons was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated with 140 Sx.
3537'--4 1/2" Production casing cemented on bottom with 125 Sx. no plug
back, no perforations.

Sand well back to 3525' and set 3 Sx. cement with dump bailer. Pull 4 1/2"
casing and squeeze well with 5 sacks hulls, 25 sacks gel and 135 Sx.
cement, staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent