



15-147-20084-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 29 1969  
CONSERVATION DIVISION  
Wichita, Kansas

12-29-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Parks of Gabbert & Jones has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Rosen Oil Co.

Complete Address: 260 Sutton Place Wichita, Ks.

Lease Name: Neilson "B" Well No. 1

Location: SW SW SE Sec. 3 Twp. 5 Rge. (E)(W) 20

County: Phillips Total Depth 3556' Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Parks was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 750' and displace  
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo F. M... ..  
Conservation Division Agent