

State of Kansas



15-137-20009-00-00

State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 6 1967

11-6-67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Howard Alexander,

Complete Address: Kennedy Building, Tulsa, Oklahoma.

Lease Name: Kemper Well No. 1

Location: SW-SE-NE Sec. 22 Twp. 5 Rge. (E)(W) 21

County Norton Total Depth 3592' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

216'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
Dakota section from 1280' to 1495'.

Circulate hole with heavy mud. Pull DP to 1515' and displace 100 Sx.  
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

Very truly yours,

H. L. Nichols  
Conservation Division Agent