



15-137-00734-00-00

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 - 1965

8-4-65

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this

date requested permission to plug the following described well:
Varn Petroleum Co.

Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Varn Petroleum Company,

Complete Address: 310 South Sutton Place, Wichita, Kansas.

Lease Name: Kemper Well No. 1

Location: SE-SE-SW Sec. 22 Twp. 5 Rge. (E)(W) 21

County Norton Total Depth 3625 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

215'--8 5/8" Surface pipe cement circulated with 160 Sx.

3619'--5 1/2" Production casing cemented with 100 Sx. No plug
back, no perforations.

Sand well back to 3610' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing to 600' and circulate heavy gel mud. Pull 5 1/2"
to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 210'
and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @
35' and 10 Sx. cement to bottom very early hours,

A. L. Nichols
Conservation Division Agent