



15-137-00621-00-00

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1965
CONSERVATION DIVISION
Wichita, Kansas

7-6-65

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Owen Bailey of Santa Fe Pipe & Supply has this date requested permission to plug the following described well:

Mr. Varn Petroleum Co.,
Mr. Bailey guarantees payment of the plugging fee.

Operator's full Name: Varn Petroleum Company,

Complete Address: 310 Sutton Place, Wichita, Kansas.

Lease Name: Kemper Well No. 2

Location: NW-SE-SW Sec. 22 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3676 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Bailey was instructed to plug the well as follows:

209'--8 5/8" Surface pipe, cement circulated with 150 Sx.
3676'--5 1/2" Production casing cemented with 75 Sx. Well
plugged back to 3450'. Top perforations @ 3338' to 3344'.

Sand well back to 3325' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to
540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 200' and
displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 35'
and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Zschale
Conservation Division Agent