

15-147-00593-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Phillips County, Sec. 30 Twp. 5S Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines 2310' FNL & 2310' FEL  
Lease Owner Cities Service Oil Company  
Lease Name Bailey "A" Well No. 2  
Office Address Box 553 Russell, Kansas 67665  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 8-23 19 47  
Application for plugging filed 10-1 19 71  
Application for plugging approved 10-6 19 71  
Plugging commenced 11-29 19 71  
Plugging completed 12-3 19 71  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 10-1 19 71  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leo Massey  
Producing formation Reagan Depth to top 3616' Bottom 17' Pen. Total Depth of Well 3633 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	197'	None
				5 1/2"	3616'	614'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Ran sand to 3600' and dumped 5 sx. cement @ 3600', Shot pipe and pulled 19 Joints. Squeezed well with 2 sx. gel, 15 sx. hulls, and 100 sx. Pozmix cement.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 20 1971

CONSERVATION DIVISION  
Wichita, Kansas

12-20-71

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.  
Address P. O. Box 405 Chase, Kansas 67524

STATE OF Kansas, COUNTY OF Russell, ss.

E. W. Peterman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. W. Peterman*


Box 553 Russell, Kansas 67665  
(Address)

Subscribed and sworn to before me this 17th day of December, 19 71

10-5-72

*James F. Kyger*

Notary Public.



15-147-00593-00-00

Geol. 63 500 5-47

WELL RECORD

Company Cotton Service (I) Co. Well No. 2 Farm Ballay

Location 330°N and 330° E of Center Sec. 10 T 5 R. 20W

Elevation 2000 (2150 (ft.)) County Phillips State Kansas

Drig. Comm. 6-2-47 Contractor H. W. Bine Drilling Co.

Drig. Comp. 7-3-47 Acid None

T. D. 3633' Initial Prod. Hydro. potential: 57 oil, 20 water, 21 hours, (6-2-47).

CASING RECORD

8-5/8" @ 197' with 175 neck cement  
200' O.C.  
5-1/2" @ 3616' with 150 neck cement

FORMATION RECORD

Clay and sand	0-197
Shale	1763
Anhydrite	1770
Shale and shells	2085
Shale and lime	2210
Lime and shale	2480
Shale and shells	3140
Lime and shale	3315
Lime	3512
Sand	3513

3613 Rotary T.D. = 3617 S.L.M.  
3633 T.D.

Curr. Top Landing	3383'
Curr. Top Anhydrite	3616'
Penetration	17'
Total Depth	3633'

Fill-up  
75° oil in 1/2 hour at 3633.  
250° oil in 4 1/2 hrs. at 3633.  
550° oil in 1 1/2 hrs. at 3633'.

	Hydro
2500'	00
2000'	00
2500'	10
3000'	20

7-7/8" Rotary Hole.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 6 1971  
CONSERVATION DIVISION  
Wichita, Kansas

10-6-71