

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior, Inc.
 Address: P.O. Box 399
 Phone: (785) 398-2270 Operator License #: 4058
 Type of Well: SWD Docket #: D-24,160
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 11/16/04 (Date)
 by: Mike Maier (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Cedar Hill Sand Depth to Top: 960' Bottom: 1000' T.D. 1410'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 135-22864 - 00-00
 Lease Name: Foos
 Well Number: 3 SWD
 Spot Location (QQQQ): NE - SW - NE - SE
1815 Feet from North / South Section Line
825 Feet from East / West Section Line
 Sec. 5 Twp. 19 S. R. 21 East West
 County: Ness
 Date Well Completed: 7/15/85
 Plugging Commenced: 11/16/04
 Plugging Completed: 11/17/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Cedar Hill Sand	water	960'	1000'	8 5/8"	365'	None
				5 1/2"	1410'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Mix 15 sacks of cement and pump down 8 5/8" Braden head and pressure to 400 psi and held. Mix 100 sacks of cement with 300# of hulls in lead in cement and pump down 5 1/2, max pressure 250 psi, shut in with slight vacuum. Return next day and top off with 20 sacks of cement. Job complete. All cement was 60/40 POZ 6% gel.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382
 Address: N. Highway 283, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: American Warrior, Inc.
 State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) 210 Avenue A, Bazine, KS 67516



and SWORN TO before me this 18th day of November, 20 04

Bernice Moore My Commission Expires: 2/17/06
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 19 2004
KCC WICHITA

[Handwritten mark]