

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market - Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-189-10012-0000

LEASE NAME COMER

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to GORS. Div.  
office within 30 days

WELL NUMBER 2-6

1329' FNL Ft. from S Section Line *KCC BEM 11/29/04 RBDMs CP-1*

1242' FEL Ft. from W Section Line

SEC. 6 TWP. 31S RGE. 37W (E) or (W)

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

COUNTY GRANT

PHONE # (72) 444-9001 OPERATORS LICENSE NO. 4824

Date Well Completed 5/21/19/63 *KCC BEM 11/29/04 RBDMs*

Character of Well GAS

Plugging Commenced 11/15/04

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Plugging Completed 11/16/04

The plugging proposal was approved on 8/03/04, 11/15/04 (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation COUNCIL GROVE Depth to Top 3048' KB Bottom 2805' T.D. 5856'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
COUNCIL GROVE	GAS	2733'	2798'	8 5/8"	1708'	0
				4 1/2"	2989'	1753'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

11/12-15/04 P&A Op witnessed by K. Jehlik, KCC. POOH tbq, rods, subs. Cmtr to 4 1/2" csg, 1850' free pipe. Load hole w/40 bbl 9ppg 36cp mud, cut csg 1753'. Circ w/50 bbl mud + 50 sx cmt plug 1740'-1590'. Disp w/24 bbl mud. Pmp 30 sx cmt plug 600'-500' disp w/7 bbl mud. Load hole to 40' w/9 ppg mud. Pmp 10 sx cmt plug from 40'-0'. Cut 8 5/8" csg 3' bgl, weld trash cover ID plate. RDMO.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

RECEIVED

Address RT. 1, BOX 49BA TYRONE OK 73951-9731


NOV 24 2004

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

KCC WICHITA

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 20 04

My Commission Expires: 4/2/2005

Notary Public