

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-00599-00-00

Well was completed on:

API NUMBER 10-5-1942

LEASE NAME State B

WELL NUMBER 1

330 Ft. from S Section Line

1650 3630 Ft. from ^W Section Line

SEC. 30 TWP. 5S RGE. 20 (W)

COUNTY Phillips

Date Well Completed 10-5-47

Plugging Commenced 5-11-88

Plugging Completed 5-11-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 31, 1988 (date)

by Mr. Dennis Hamel of District #4 (KCC District Agent's Name).

Well was completed on: 10-5-47
Is ACO-1 filed? 10-5-47 If not, is well log attached? yes

Producing Formation Reagan Depth to Top 3642 Bottom 3653 T.O. 3692

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Reagan	Oil	3642	3653	8-5/8"	155'	0
				5-1/2"	3675'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section.
Perf. Anhydrite at 1780 w/4 SPF & below the Dakota at 1060' w/3' SPF. Tied onto the 5-1/2" csg. & filled it to surf. w/250 sx 65/35 cmt. w/10% gel & 2% Econo. & 4 sx hulls. Tied onto the 8-5/8" csg. & filled the annulus to surf. w/75 sx cmt. + 1 sx hulls.
State witness: Mr. Dennis Hamel

(If additional description is necessary, use BACK of this form.)
RECEIVED
STATE CORPORATION COMMISSION

Name of Plugging Contractor Halliburton Oil Service License No. _____

Address Oberlin, KS 67749 AUG 10 1988 8-10-88

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma CONSERVATION DIVISION
Wichita, Kansas
55.

(Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed in
the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 27th day of July, 19 88

Marsha C. Wilson
Notary Public

My Commission Expires: 4-1-92