

15-147-00601-00-02

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-147-09-11-46

LEASE NAME States "B"

WELL NUMBER 3

TYPE OR PRINT
NOTICE: Fill out completely
and return to Comm. Div.
office within 30 days.

1650 ft. from S Section Line

3630 ft. from E Section Line

SEC. 30 TWP. 05 RGE. 20 (S) or (W)

COUNTY Phillips

Date Well Completed 09/24/46

Plugging Commenced 11/05/96

Plugging Completed 11/05/96

LEASE OPERATOR OXY USA Inc.

ADDRESS P.O. Box 300; Tulsa, OK 74102-0300

PHONE # (918) 561-2211 OPERATOR'S LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply)

The plugging proposal was approved on October 22, 1996 (date)

by Dennis L. Hamel

Is ACO-1 file? No If not, is well log attached? Yes

Producing Formation Reagan Depth to Top 3654' Bottom 3656' T.D. 3656'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out
Reagan	Oil	3654'	3656'	8-5/8"	203'	0
				5-1/2"	3654'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Dug out csg and orange peeled 5-1/2" to 8-5/8" csg. Install 2" riser to surface. Rigged up H.L.S. & perf at 1160' and 1800' with 2 spf. MIRU Murfin Drilling, RIH with 2-3/8" tbg. Open ended to 3620'. Pumped 45 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled to 2600'. Pumped 45 sxs cement & 100# hulls. Pulled tbg to 1600'. Pumped 45 sxs cement with 100# hulls. (continued on back)

Name of Plugging Contractor Halliburton Energy Services License No. 5287

Address 1102 E. 8th St.; Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Kansas COUNTY OF Rooks, ss.


Kenneth R. Curry (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Drawer D; Plainville, KS 67663

FEB 18 1997
2-18-97
SUBSCRIBED AND SWORN TO before me this 14 day of February, 1997
CONSERVATION DIVISION
WICHITA, KS

[Signature]
Notary Public



My Commission Expires: May 20, 2000

Additional plugging report information for States "B" #3

Pulled to 600' and pumped 40 sxs cement and circulated to surface. POOH with rest of tbq. Hooked up to 5-1/2" casing and pumped 20 sxs cement. Max PSI 475. SIP 400 PSI. Hooked up to 8-5/8" csg and pumped 40 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max PSI 100. SIP 50 PSI. Total 250 sxs cement used.