

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION  
Address: 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226  
Phone: (316) 682-1537 Operator License #: 5030  
Type of Well: ENHR Docket #: E-3145  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Topeka Depth to Top: 2983 Bottom: 3154 T.D. \_\_\_\_\_  
LKC Depth to Top: 3207 Bottom: 3426 T.D. 3556  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. 3571

API Number: 15-163-03,553-00-01  
Lease Name: Krueger Unit  
Well Number: 104W  
Spot Location (QQQQ): \_\_\_\_\_ - NW - SW - SW  
990' Feet from  North /  South Section Line  
4290' 4950 Feet from  East /  West Section Line  
Sec. 35 Twp. 10S S. R. 16W  East  West  
County: Rooks  
Date Well Completed: 4/4/51  
Plugging Commenced: 9/29/04  
Plugging Completed: 9/29/04

*KCC  
BEM  
11/10/04  
RBDMS  
Connected  
10/18/04  
KCC  
BEM  
11/10/04  
RBDMS  
CP 2/3*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	280'	none
				5-1/2"	3560'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf'd @ 1950', 1260', 825' w/2 SPF. TIH w/tbg to 2220'. Spotted 80 sx cement w/200# hulls.  
Pulled tbg to 1200' and circulated cement to surface w/100 sx cement . TOH with tbg.  
Connected to 8-5/8" and pressured immediately to 500#. Connected to 5-1/2" and pumped 20 sx cement, MP - 900#.  
SIP - 900#. Pumped total of 200 sx 60/40 poz with 10% gel. Approved by Dennis Hamel w/KCC.


Name of Plugging Contractor: Allied Cementing Co., Inc. License #: 68320  
Address: P.O. Box 31, Russell, KS 67665-0031

Name of Party Responsible for Plugging Fees: Vess Oil Corporation  
State of Kansas County, Sedgwick, ss.

Pat Canaday (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) 8100 E. 22nd Street North, Bldg. 300, Wichita, KS 67226

SUBSCRIBED and SWORN TO before me this 15th day of October  
Michelle D. Henning My Commission Expires \_\_\_\_\_  
Notary Public



*per*

