

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: John H. Shaida  
Address: 4126 N. Sweet Bay Circle, Wichita, KS 67226  
Phone: (316) 636-2525 Operator License #: 3833  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 10.29.04 (Date)  
by: Herb Dienes & Pat Staab/Hays, KS (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing/KC Depth to Top: 3176 Bottom: 3395 T.D. 3449  
Arbuckle Depth to Top: 3436 Bottom: \_\_\_\_\_ T.D. 3449  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-051-05437-00-00  
Lease Name: Froelich "E"  
Well Number: 8  
Spot Location (QQQQ): NW - NE - SE -  
2310 Feet from  North /  South Section Line  
990 Feet from  East /  West Section Line  
Sec. 27 Twp. 12 S. R. 16  East  West  
County: Ellis  
Date Well Completed: May, 1954  
Plugging Commenced: 11.01.2004  
Plugging Completed: 11.01.2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing/KC	oil	3176	3395	7	3443	-0-
Arbuckle	oil	3436		10.75	243	-0-
				4.5 (liner)	1212	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforate @ 1725' & 1225'. Run tubing to 2100'; 1st plug (200 sx) @ 2100' with hulls. Pull tubing up to 1200'.

Pump cement w/hulls (107 sx). Pull tubing to 700'. Pump 27 sx. Circulate. Pull tubing out of hole. Hook-up to surface, pump 3 sx.


Hook-up to liner, pump 32sx. Top off.

Name of Plugging Contractor: Express Well Service - Swift Services, Inc. License #: 6426  
Address: P.O. Box 426, Victoria, KS 67671

Name of Party Responsible for Plugging Fees: John H. Shaida  
State of Kansas County, Sedgwick, ss.

John H. Shaida (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_  
(Address) 4126 N. Sweet Bay Circle, Wichita, KS 67226



SUBSCRIBED and SWORN TO before me this 20th day of November, 20 04  
My Commission Expires: 1-16-2005  
Notary Public \_\_\_\_\_

RECEIVED  
DEC 01 2004  
KCC WICHITA