

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: DaMar Resources, Inc.
 Address: P. O. Box 70
 Phone: (785) 625-0020 Operator License #: 9067
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 11/1/2001 (Date)
 by: Mike Maiers (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Lansing-Kansas City Depth to Top: 3985 Bottom: 4319 T.D. _____
Pawnee Depth to Top: 4450 Bottom: 4478 T.D. _____
Cherokee Sand Depth to Top: 4577 Bottom: 4588 T.D. 4675

API Number: 15-101-21,156-00-00
 Lease Name: S. McBee *KCC BEN 11/30/04 RBDMS*
 Well Number: one /
 Spot Location (QQQQ): C - SE - SE - NE
2310 Feet from North / South Section Line
330 Feet from East / West Section Line
 Sec. 29 Twp. 17 S. R. 27 East West
 County: Lane *6-1-1985 KCC BEN 11/30/04 RBDMS*
 Date Well Completed: 5/13/85
 Plugging Commenced: 11/4/2004
 Plugging Completed: 11/4/2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	428	0
				5 1/2*	4677	0
* two staged from 1250	- surface w/215 sx					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spot 75 sx common w/3% cc and 300# hulls @ 4200. Spot 40 sx common w/3% cc @ 2000. Spot 150 sx 60/40 poz 6% gel @ 1600' - circulated cement to pit. Top off casing w/25 sx 60/40 poz 6% gel


Name of Plugging Contractor: Allied Cementing License #: 115725 9999L
 Address: P. O. Box 31 Russell, KS 67665

Name of Party Responsible for Plugging Fees: DaMar Resources, Inc.
 State of Kansas County, Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) 234 W. 11th St. Hays, KS 67601

SUBSCRIBED and SWORN TO before me this 22 day of November 20 04
[Signature] My Commission Expires: _____
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 24 2004
KCC WICHITA

BM