

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Berexco Inc.

Address: P.O. Box 20380 Wichita, KS 67208

Phone: (316) 265-3311 Operator License #: 05363

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/15/04 (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 4685' Bottom: 4706' T.D. 4706'

API Number: 15-NA083-10008-00-00

Lease Name: Schraeder

Well Number: 3

Spot Location (QQQQ): _____ - SW - SW - NE

2310 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 3 Twp. 24 S. R. 24 East West

County: Hodgeman

Date Well Completed: 12/51

Plugging Commenced: 11/15/04

Plugging Completed: 11/17/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Mississippi	Oil & Water	0	377'	8 5/8"	377'	0
		0	4685'	5 1/2"	4685'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

25 sx w/200# hulls @ 4500', 40 sx w/200 hulls @ 2816', 50 sx @ 1580', Perf 5 1/2" casing @ 804'. Set retainer @ 700' & squeezed holes @ 804' w/100 sx. Circulated 60 sx from 700' to surface. Pumped 6 sx down 5 1/2" x 8 5/8" annulus.

Name of Plugging Contractor: Whitetail Crude Inc. License #: 31627

Address: Box 544 Ness City, KS 67560


Name of Party Responsible for Plugging Fees: Berexco Inc.

State of KANSAS County, SEDGWICK, ss.

Evan C. Mayhew (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Evan C. Mayhew

(Address) P.O. Box 20380 Wichita, KS 67208



SUBSCRIBED and SWORN TO before me this 30th day of November, 2004

Diana E Plotner My Commission Expires: Aug 10, 2007
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 01 2004
KCC WICHITA

bm