

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Berexco Inc. Address: P.O. Box 20380 Wichita, KS 67208 Phone: (316) 265-3311 Operator License #: 05363 Type of Well: Oil Docket #: The plugging proposal was approved on: 11/17/04 by: Steve Durrant Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Mississippi Depth to Top: 4522' Bottom: 4530' T.D. 4556' Marmaton Depth to Top: 4297' Bottom: 4302' T.D. 4556' Lansing Depth to Top: 4123' Bottom: 4126' T.D. 4556'

API Number: 15-NA 083-00078-00-00 Lease Name: Gus Miller A Well Number: 9 Spot Location (QQQQ): - NE - NE 660 Feet from North / South Section Line 660 Feet from East / West Section Line Sec. 7 Twp. 22 S. R. 22 East West County: Hodgeman Date Well Completed: 3/62 Plugging Commenced: 11/17/04 Plugging Completed: 11/23/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Mississippi, Marmaton, and Lansing formations.


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set. 25 sx w/200# hulls @ 4123', 25 sx w/200# hulls @ 2790', 50 sx w/4% CC @ 1891'. Perforated 5 1/2" @ 600', pumped 130 sx down csg & filled csg to surface. Pumped 30 sx down 5 1/2" x 8 5/8" annulus. All cement was 60/40 poz 6% gel.

Name of Plugging Contractor: Whitetail Crude Inc. License #: 31627 Address: Box 544 Ness City, KS 67560

Name of Party Responsible for Plugging Fees: Berexco Inc. State of KANSAS County, SEDGWICK, ss.

Evan C. Mayhew (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) P.O. Box 20380 Wichita, KS 67208



SUBSCRIBED and SWORN TO before me this 30th day of November, 2004. My Commission Expires: Aug 10, 2007

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED DEC 01 2004 KCC WICHITA