

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Webco Oil Company
Address: 2136 NE 90th Ave., Hoisington, KS 67544
Phone: (620) 587-3539 Operator License #: 6357
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: November 21, 2004 (Date)
by: Pat Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 2872' Bottom: 3325' T.D. 3326'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 167-21,774 - 00 - 00
Lease Name: Kaufman E *KCC BEM*
Well Number: #1 *12/3/04 RBDMS*
Spot Location (QQQQ): NW - SW - SW -
990' Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 36 Twp. 15 S. R. 12 East West
County: Russell
Date Well Completed: 9/7/1981
Plugging Commenced: 11/22/04
Plugging Completed: 11/23/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	342'	8-5/8"	352'	0'
	Production	0'	3316'	5-1/2"	3316'	558.65'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Backhoe and operator leveled location, dug cellar and pit. M.I.R.U. Ran bailer to bottom. Spot sand. Only got 20 bbls. of fluid in hole. Fluid was 800' from surface. M.I.R.U. casing jacks. Rigged up tongs and laid down line. Spot 5 sxs cement on bottom. Pulled casing out of slips. Started to work casing and casing parted. Called State for orders. Pulled 1 joint and waited for Copeland. Pumped first plug and trip out of hole with rest of casing. Top well off. Cleaned up equipment, rigged down and loaded up casing jacks. Recovered 558.65' of 5-1/2" casing.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901
Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: Webco Oil Company
State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt Expires 4/13/06

(Signature) Edward S. Nemnich
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 24th day of November, 20 04

Juan J. Mitchell My Commission Expires: 4/13/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
DEC 01 2004
KCC WICHITA

Bu