

75-137-00001-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Norton County, Sec. 21 Twp 5S Rge. 21W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE SW

Lease Owner D & D Drilling Company

Lease Name Williams Well No. 1

Office Address 308 Schweiter Building Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed by D & D Drilling Company 19

Application for plugging approved 19

Plugging commenced 8-11-63 19

Plugging completed 8-23-63 19

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? by D & D Drilling Company

Name of Conservation Agent who supervised plugging of this well W. L. Nichols

Producing formation Depth to top Bottom Total Depth of Well PB 3681 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	210'	None
				5 1/2	None	1313'

8-30-63  
**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 30 1963

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

CONSERVATION DIVISION  
Wichita, Kansas

Cleaned out cellar. Measured T.D. Sanded to 3670'. Dumped 5 sacks of cement. Shot well at 2909'. Loaded hole.

Setting up unit. Working pipe. Spotting oil.

Shot well at 2611'. Working pipe. Shot well at 2000'. Working pipe. Shot well at 1800'. Working pipe.

Shot well at 1422'. Working pipe. Shot well at 1300'. Working pipe.

Pulling pipe.

Plugging well at 550'. Circulating mud. Spotted 20 sacks of cement to 230'. Spotted another 20 sacks of cement and capped well with 10 sacks of cement.

Pulling pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes

P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28 day of August, 1963

My commission expires May 27, 1964

Notary Public.