

15-137-00210-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Norton County. Sec. 15 Twp. 5 Rge. 21 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Honaker-Davis Drlg. Co.
Lease Name Glennemeier Well No. 1
Office Address 2008 Lakin, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-13 19 59
Application for plugging filed 3-13 19 59
Application for plugging approved 3-13 19 59
Plugging commenced 5:30 P.M. 3-13 19 59
Plugging completed 8:00 P.M. 3-13 19 59
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3630 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	218	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud to 600'. Set plug. Mixed 15 sacks cement by hand and poured through drill pipe.
Filled hole with heavy rotary mud to 210'. Set plug. Dumped in 1/3 sack hulls. Mixed 20 sacks cement by hand and poured through drill pipe.
Filled hole with heavy rotary mud to 40'. Set plug. Dumped in 1/3 sacks hulls. Mixed 10 sacks cement by hand and filled hole to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor
Address

STATE OF Kansas, COUNTY OF Barton, ss.
S. C. Lingreen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. C. Lingreen
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 59
My commission expires 6-25-59
Kenneth G. Fischer, Notary Public.

PLUGGING
FILE SEC. 15 T. 5 R. 21 W
BOOK PAGE 24 LINE 33

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY

Company- HONAKER-DAVIS DRIG. CO. ET AL
Farm- Glennemeier No. 1

SEC. 15 T. 5 R. 21W
NW NW SE

Total Depth. 3630'
Comm. 3-5-59 Comp. 3-13-59
Shot or Treated.
Contractor. Honaker-Davis Drig.
Issued. 7-11-59

County Norton
KANSAS



CASINO:

8 5/8" 218' cem w/200 sk.

Elevation. 2176' RB

Production. Dry

Figures indicate Bottom of Formations.

top soil & post rock	80
clay & sand	126
blue shale	218
shale & shells	1450
sand	1550
red bed & shale	1775
Anhydrite	1812
shale & shells	1975
shale w/lime strks	2040
shale & lime	2225
lime & shale	3108
lime	3230
lime & shale	3378
lime	3435
lime w/chert strks	3493
lime	3630 RTD
Total Depth	

TOPS:

Heebner	3332
Toronto	3357
Lansing-Kansas City	3372
Base Kansas City	3558
Reagan	3620

DST #1 3340-3435', op 60 mins, closed 20 min.
good blow, rec. 585' muddy water, BHP 1120#,
FP 60-385#.

DST #2 3527-3558', op 20 mins, closed 20 mins.
weak blow 10 mins., rec. 15' mud. BHP 740#.

DST #3 3624-3630', op 60 mins., closed 20 mins.
strong blow, rec. 2210' water, BHP 1000#,
FP 400-1000#.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION
Wichita, Kansas

7-16-64