

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-137-20415-00-00

LEASE NAME Kemper

WELL NUMBER #1

990' Ft. from S Section Line

4290' Ft. from E Section Line

SEC. 14 TWP. 5S RGE. 21W (E) or (W)

COUNTY Norton

Date Well Completed 6/9/00

Plugging Commenced 6/9/00

Plugging Completed 6/9/00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Thoroughbred Associates, LLC

ADDRESS 8100 E. 22nd St. No. Bldg. 600 Wichita KS 67226

PHONE#( ) 685 1512 OPERATORS LICENSE NO. 31514

Character of Well P&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/9/00 (date)

by Herb Deines, Hays Office (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation N/A Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
DATE CORP. COMMISSION  
JUN 06 2000  
7-6-2000  
CONSERVATION DIVISION  
Wichita Kansas

Formation	Content	From Surf	To	Size	Put in	Pulled out
			242	8-5/8"	235'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set:  
Plugged with a total of 225 sxs of 60-40 pozmix, 6% gel. 1st plug set at 3556' w/25 sxs; 2nd plug set at 1750' w/25 sxs; 3rd plug set at 1050' w/100 sxs; 4th plug set at 295' w/40 sxs; 5th plug set at 40' w/100 sxs; and 15 sxs in rathole, 10 sxs in mousehole. Completed at 11:45 PM 6/9/00

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address \_\_\_\_\_

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Thoroughbred Associates, LLC

STATE OF Kansas COUNTY OF Sedgwick, ss.

Robert C. Patton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) 8100 E. 22nd St. No. Bldg. 600 Wichita, Kansas 67226

SUBSCRIBED AND SWORN TO before me this 5th day of July, 192000

[Signature]  
Karri Wolken Notary Public

My Commission Expires: July 31, 2000

