

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: VAL Energy Inc.  
Address: Box 116, Wichita, KS 67201  
Phone: (316) 263-6688 Operator License #: 5822  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 191-22,015-0000  
Lease Name: Susie Duncan  
Well Number: 2  
Spot Location (QQQQ): S2 NE - SE - SW *KCC 130m 11/30/04 R5DM5*  
800 Feet from  North /  South Section Line  
2970 Feet from  East /  West Section Line  
Sec. 7 Twp. 30S S. R. 2W  East  West  
County: SUMNER  
Date Well Completed: \_\_\_\_\_  
Plugging Commenced: 11-02-04  
Plugging Completed: 11-03-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	330	
				5 1/2	3310	2635

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Checked hole sand at 3140', bailed 5 sacks of Portland, ripped at 2805', 2635', worked free, pulled to 600', pumped 35 sacks, pulled to 400', pumped 35 sacks, pulled to 250', pumped 49 sacks.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925  
Address: 401 West Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: VAL Energy Inc.

State of Kansas County, Sedgewick, ss.

K Todd Allom (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature)

(Address)

K Todd Allom  
Box 116 Wichita, KS 67201

SUBSCRIBED and SWORN TO before me this 29 day of November 2004

Gary D. Stearns My Commission Expires: \_\_\_\_\_  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
NOV 30 2004  
KCC WICHITA

*Bm*

# Quality Well Service, Inc.

401 West Main  
Lyons, KS 67554

# Invoice

Date	Invoice #
11/24/2004	612

Bill To
VAL Energy Inc. Box 116 Wichita, KS 67201

P.O. No.	Terms	Lease Name
		Susie Duncan #2

Description	Qty	Rate	Amount
Rig Time	13	135.00	1,755.00T
Trucking Floor	1	90.00	90.00T
Sand	1	35.00	35.00T
Cement	5	9.00	45.00T
Ripping of Pipe	2	140.00	280.00T
Torch	1	35.00	35.00T
Water Truck	4	60.00	240.00T
Backhoe	2.5	62.00	155.00T
Out of Town	1	120.00	120.00T
Phone Calls	1	10.00	10.00T
Clerical Fees	1	10.00	10.00T
Wiping Rubber	1	15.00	15.00T
11-02-04 Rigged up, checked hole, sanded bottom, loaded hole, dug cellar, tore head down, set floor, pulled slips, cut surface off, went to room.			
11-03-04 Checked hole sand at 3140', bailed 5 sacks of Portland, ripped 2805', worked pipe, no gain, ripped 2635', worked free, pulled to 600', pumped 35 sacks, pulled to 400', pumped 35 sacks, pulled to 250', pumped 49 sacks, pulled rest of pipe out, tore down, loaded out.			
<b>Subtotal</b>			\$2,790.00

RECEIVED  
NOV 30 2004  
KCC WICHITA

<b>Sales Tax (6.8%)</b>	\$189.72
<b>Total</b>	\$2,979.72

# United Cementing & Acid Company, Inc.

2510 W. 6th St.

El Dorado, Kansas 67042

316-321-4680 800-794-0187 (Fax) 316-321-4720

Customer:


Val Energy, Inc.  
PO Box 116  
Wichita, KS 67201-0116

Invoice No. 6387

Field Ticket 5767

Date 11/10/2004

PO#



Date of Job	County	State	Lease	Well No.
11/03/04	SU	KS	Suzy Duncan	#2
Size of Casing	Depth Of Well	Depth Of Job	Plug Depth	Pressure
5-1/2"				
Quantity	Description	Unit Price		Total
	<b>OLD HOLE PLUG</b>	UOM		
119	60/40 Pozmix	sax	4.90	583.10
8	Gel	sax	9.70	77.60
300#	Cottonseed Hulls	cwt	28.70	86.10
127	Bulk Charge	sax	0.98	124.46
	Drayage - 6.35 tons			292.04
63	Mileage charge	mi	2.05	129.15
	Cement Unit			500.00
<i>Thank you for your continued business</i>				
	<b>Taxable</b>	<b>*Non-Taxable</b>	<b>Tax Rate</b>	<b>Sales Tax</b>
	1792.45	0.00	0.053	95.00
				<b>TOTAL DUE</b>
				<b>\$1,887.45</b>

RECEIVED  
NOV 30 2004  
KCC WICHITA

TERMS: Net 30 days from invoice date. Please pay from this invoice.

ORIGINAL INVOICE

# United Cementing and Acid Co., Inc.

6357

## SERVICE TICKET

5767

Oil Well Cementing & Acidizing  
 (316) 321-4680 • 800-794-0187 • FAX (316) 321-4720  
 2510 West 6th Street • El Dorado, KS 67042

DATE 11-3-2011

COUNTY Sumner CITY \_\_\_\_\_

CHARGE TO Val Energy

ADDRESS \_\_\_\_\_ CITY \_\_\_\_\_ ST \_\_\_\_\_ ZIP \_\_\_\_\_

LEASE & WELL NO. Suzzy Duncan #2 CONTRACTOR Quality Well Serv.

KIND OF JOB Old hole plug SEC. \_\_\_\_\_ TWP. \_\_\_\_\_ RNG. \_\_\_\_\_

DIR. TO LOC. Viola, SE, 35, 1 1/2 W, N Into 1.00  OLD  NEW

Quantity	MATERIAL USED	Serv. Charge	
119.5x	60/40 poz 4% gel @4.94		500.00
85x	gel @9.70		583.14
300 lbs	CSH @ 28.70 cwt.		77.60
			810.10
127.5x	BULK CHARGE		124.46
63	BULK TRK. MILES <u>6.35 tons</u>		209.04
63	PUMP TRK. MILES		129.15
	PLUGS		
		1530. SALES TAX	95.00
		TOTAL	1887.45

RECEIVED  
 NOV 30 2011  
 KCC WICHITA

T.D. \_\_\_\_\_ CSG. SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_

SIZE HOLE \_\_\_\_\_ TBG SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_

MAX. PRESS. \_\_\_\_\_ SIZE PIPE 5 1/2"

PLUG DEPTH \_\_\_\_\_ PKER DEPTH \_\_\_\_\_

PLUG USED \_\_\_\_\_ TIME FINISHED 2:30

REMARKS: Pulled 5 1/2 casing out to 600ft. Brake circulation, Mix + pump 35x60/40 poz 4% gel + 100# CSH + disp. Pulled 5 1/2' up to 400ft, Brake circulation, Mix + pump 35x60/40 poz 4% gel - 100# CSH + disp. Pull 5 1/2" up to 250ft. Brake circulation, Mix + pump. 49.5x60/40 poz 4% gel + 100# CSH to surface, Cement stayed in cells.

### EQUIPMENT USED

NAME Josh Creely P-10  
James R. Thomas #26  
 CEMENTER OR TREATER

NAME Jerry Hudson P-3  
 OWNER'S REP.