

15-147-00003-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Phillips County, Sec. 34 Twp. 5 Rge 20 (E) (W) X

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW%SW%" or footage from lines SW SW NE  
Lease Owner Messman-Rinehart Oil Co.  
Lease Name Steel Est. Well No. #1  
Office Address 518 Petroleum Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 7-27-62 19\_\_\_\_  
Plugging completed 8-1-62 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3675' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back to 3425', mixed and dumped 3 sacks cement.  
Pumped 24 sacks jell at 550' - pulled pipe to 150', mixed and ran 20 sacks cement,  
pulled pipe out, mixed and ran 20 sacks cement for top cap.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 6 1962  
CONSERVATION DIVISION  
Wichita, Kansas  
8-6-62

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 3 day of August, 19 62

My commission expires 24 October 1964  
Sidney D. Miller Notary Public.



ROTARY DRILLING LOG

15-147-00003-00-00

Operator: Messman-Rinehart Oil Co.  
 No. 1 Steele Estate  
 C SW SW NE  
 Sec. 34-5S-20W  
 Phillips County, Kansas

CONTRACTOR: Rains & Williamson Oil Co.  
 COMM: 5/21/62  
 COMP: 5/31/62

Remarks: set 8 5/8" @ 215' with 135 sacks

set 5 1/2" @ 3575' with 75 sacks common cement and 1 sack jel.

Formations:

Surface soil	30°
Shale	170°
Lime and Shale	215°
Plug and cement	190°
Cement	215°
Shale	1285°
Shale and Lime Shells	1686°
Shale	1715°
Lime	1746°
Shale & Lime	1975°
Shale & Lime	2186°
Shale & Lime	2429°
Shale & Lime	2660°
Shale & Lime	2780°
Shale & Lime Shells	2915°
Shale & Lime	3070°
Shale & Lime	3180°
Shale & Lime	3275°
Lime	3349°
Lime	3400°
Lime	3460°
Lime	3501°
Lime	3526°
Lime	3553°
Sand - Shale	3585°
Lime	5593°
Lime	3603°
Lime	3615°
Lime	3670°
3678 (Rotary TD)	TD

8-9-62  
**RECEIVED**  
 STATE CORPORATION COMMISSION  
 AUG 9 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

By: *Wilson Rains*  
 Wilson Rains  
 Partner

15-147-00003-00-00


COMPLETION DATA

Messner-Rinehart Oil Company  
No. 1 Steele Estate  
Ctr. SW/4 SW/4 NE/4,  
Section 34-55-20N  
Phillips County, Kansas

- 6/11/62 - Moved in cable tools, Subd, 10 GPPH natural - no wtr.  
Perf. 3501-03' w/4<sup>5</sup> ft.; perf. 3506-02' w/4<sup>5</sup> ft.; perf.  
3514-18' w/4<sup>5</sup> ft., treated with 750 gal. acid, Sub.  
.89 BPPH (10% load wtr.)
- 6/12/62 - Treated with 2500 gal. job acid, pressured up to 1200#.  
Sub. .83 BPPH - 4 hrs., (45 bbis. load not recovered)  
Preparing to abandon

MESSNER-RINEHART OIL COMPANY

By:

  
Roger L. Messner

RLH/bjs  
6/26/62

RECEIVED  
REGISTRATION COMMISSION  
AUG 9 1962  
CONSERVATION DIVISION  
Wichita, Kansas