

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 Colorado Derby Bldg
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-00834-00-00

API NUMBER 15-NA

LEASE NAME Ray C

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

~~4250~~ 990 ^{CD 57} Ft. from 8 Section Line

2310 Ft. from E Section Line

SEC. 32 TWP. 5S RGE. 20 (x) or (W)

COUNTY Phillips

Date Well Completed 12/10/41

Plugging Commenced 8/31/94

Plugging Completed 8/31/94

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Reagan Depth to Top 3520 Bottom 3542 T.D. 3566

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Reagan	Oil	3520	3542	8 5/8	149	
				5 1/2	3552	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Perf'd @ 1700 & 1060. RIH w/ 2 3/8 tbq to 3100. Mixed & pumped 60sks 60/40 Poz w/150# hulls. POOH w/tbq to 2100. Mixed & pumped 60sks cmt w/150# hulls. POOH w/tbq to 1100. Mixed & pumped 80sks cmt. Circ'd cmt to surface. POOH w/tbq. Hooked up to 5 1/2 csq. & pumped 50sks cmt. Shut-in press 100#. Hooked up to 8 5/8. Pumped 50sks cmt w/100# Hulls. Shut-in press 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ~~J. W. Gibson Well Service~~ High Plains License No. ~~5866~~ 8003

Address ~~505 W. Commercial, Logan, KS 67646~~ P.O. Box 307, Logan, KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

9-20-94
SEP 20 1994

(Signature) [Signature]
(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 13th day of September, 19 94

CONSERVATION DIVISION
WICHITA, KANSAS

Kay Ann Kilmer
Notary Public

My Commission Expires: 5-2-98