

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Well was completed on
API NUMBER 10-1-41

15-147-00533-00-00

LEASE NAME Rav G--

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Lin

330 Ft. from E Section Lin

SEC. 32 TWP. 5S RGE. 20 (E or W)

COUNTY Phillips

Date Well Completed 10-1-41

Plugging Commenced 10-14-87

Plugging Completed 10-14-87

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE#(405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #4

Is ACO-1 filed? completed on 10-1-41 If not, is well log attached? Yes

Producing Formation Reagan Depth to Top OH 3569' Bottom 3582' T.D. 3582'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Reagan</u>	<u>oil</u>	<u>3569</u>	<u>3582</u>	<u>8-5/8"</u>	<u>165'</u>	<u>0'</u>
				<u>5-1/2"</u>	<u>3564'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perf. 5-1/2" csg. at 1725' w/4 SPF, 1110' w/3 SPF & 170' w/3 SPF. Pumped 165 sx. cmt. & 5 sx hulls down 5-1/2" csg. Pumped 30 sx cmt. & 2 sx hulls down 8-5/8" csg.

P&A completed. State Witness: Mr. Carl Goodrow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No.

Address Oberlin, KS

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Special Projects Manager

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Del G. Oliver

3545 NW 58th Street

(Address) Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 26th day of January, 19 88

Debra Jo Howeth
Notary Public

My Commission Expires: 4-24-89

STATE CORPORATION COMMISSION

JAN 28 1988
1-28-88
CONSERVATION DIVISION
Wichita, Kansas

Form CP
Revised 08-