

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-00561-00-00

API NUMBER 15-147-97516

LEASE NAME Hansen B

WELL NUMBER #5

4950' Ft. from S Section Line

4290' Ft. from E Section Line

SEC. 33 TWP. 5s RGE. 20 (S) or (W)

COUNTY Phillips

Date Well Completed 10-7-48

Plugging Commenced 12-18-97

Plugging Completed 12-18-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA INC.

ADDRESS P.O. Box D, Plainville, KS 67663

PHONE# (785) 434-7681 OPERATORS LICENSE NO. 5447

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/18/97 (date)

by Dennis Hamel - Hays, KS (KCC District Agent's Name).

Is ACO-1 filed? On File If not, is well log attached? _____

Producing Formation Reagan Depth to Top 3556' Bottom 3560' T.D. 3560'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Reagan	Oil	3556	3560	5-1/2	3556	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

*** See attached paper ***

Name of Plugging Contractor Halliburton License No. _____

Address Hays, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA INC.

STATE OF Kansas COUNTY OF Rooks, ss.

Jim Nowell

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jim Nowell

(Address) P.O. Box D, Plainville, KS



AND SWORN TO before me this 18 day of March, 19 98

Sheryl Axelson
Notary Public

My Commission Expires: 5-20-2000

3-26-98

OXY U.S.A., Inc.
Well Chronological Report

03/18/98

HANSEN B 5

=====

12/18/97 JOB: Plug and Abandon; CMIC: Jim Nowell
MIRU Murfin Drilling. RIH W/ Logtech and Perfed at 1050' and 1925'. RIH
W/ 2 7/8" tbg to 3350'. MIRU Howco. Mixed and pumped 76 sks MidCon II
w/ 2 % cc and 300 pounds of Hulls. Fluid circulated to surface after
pumping 5 bbls. Pulled tbg to 1804', mixed and pumped 70 sks MidCon II
w/ 150 pounds of hulls. Pulled the tbg out. Hooked onto the 5 1/2" * 8
5/8" annulus. Pumped 25 sks MidCon II. Pressured to 500 PSI. Hooked up
to the 5 1/2". Pumped 20 sks MidCon II. Pressured to 500 PSI. Shut in
the casing. Rigged down Howco and Murfin Drilling.
L/E \$ 1115; MAT \$ 750; CUM: L/E \$ 1115, MAT \$ 750;

RECEIVED
STATE COMMISSION

MAR 26 1998