

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-147-00560-00-00

API NUMBER: completed on 5/27/42

LEASE NAME Hansen B

WELL NUMBER 4

2970 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 33 TWP. 5S RGE. 20 (W)

COUNTY Phillips

Date Well Completed 5/27/42

Plugging Commenced 2/18/87

Plugging Completed 2/18/87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 N.W. 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4432 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? District #6

Is ACO-1 filed? completed on 5/27/42 If not, is well log attached? yes

Producing Formation Reagan Depth to Top 3557 Bottom 3566' T.D. 3566'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Reagan	oil	3557	3566	8-5/8"	153'	
				5-1/2"	3557'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perf. Anhydrite at 1743' and Dakota at 1040' w/4 shots each. Pumped 200 sx Econolite cmt. plus 300 lb hulls down 5-1/2" csg. Pumped 200 sx cmt. + 300 lbs hulls down 8-5/8".
P & A completed. State witness: Mr. Dale Balthazor.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Service Company License No. _____

Address Oberlin, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver
3545 NW 58th Street

(Address) Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 2 day of March, 19 87

Jeresa Jo Bowth
 Notary Public

My Commission Expires: 4-24-89

MAR 3-4-87
 4:09 PM
 Form CP-4
 CONSERVATION DIVISION
 Wichita, Kansas