

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-147-00543-00-00
LEASE NAME NICHOL A

WELL NUMBER 6
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

440
330 Ft. from S Section Line
4950 Ft. from E Section Line

RECEIVED
JAN 06 2003
KCC WICHITA

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 33 TWP. 5S RGE. 20W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY PHILLIPS
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 11/6/51
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 12/10/02
Plugging Completed 12/10/02

The plugging proposal was approved on 12/10/02 (date)
By Witnessed and approved by Darrel Dipman w/KCC Hays,KS. (KCC District Agent's Name).
Is ACO-1 filed? ? If not, is well log attached? no
Producing Formation Reagan SD Depth to Top 3534 Bottom 3534 TD 3535 Show
depth and thickness of all water oil and gas formations. .

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	195	10 3/4"	195	0
		production	3533	5 1/2"	3533	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Plugged well as follows: TIH w/2 3/8" tbg to 3530'. TD @ 3535'. Pumped 100 sxs multi density cmt w/400#hulls. TOH to 1750'. Pumped 50sxs cmt w/200#hulls. Hooked to 5 1/2" csg. Pumped 32 sxs w/200# hulls. Csg. loaded wouldn't hold press. Open riser. Flushed fld to pit until good cmt. Closed riser & pumped 85 sxs w/100#huls. PSI to 300# held. 270 sxs cmt & 900# hulls total. Well P/A. Witnessed and approved by Darrel Dipman w/KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .SS.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 13th day of Dec., 2002

Notary Public - Barbara J. Dodson [Signature]
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



CR



CHARGE TO: *Muffin Dng Co*
 ADDRESS:
 CITY, STATE, ZIP CODE: *Logan Ks*

TICKET No 5113

PAGE 1 OF 1

1. SERVICE LOCATIONS <i>Hay 16</i>	WELL/PROJECT NO. <i>A-6</i>	LEASE <i>Nichol</i>	COUNTY/PARISH <i>Phillips</i>	STATE <i>KS</i>	CITY	DATE <i>12-10-02</i>	OWNER <i>Same</i>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO. <i>Muffin</i>	SHIPPED VIA <i>105</i>	DELIVERED TO <i>Logan</i>	ORDER NO.	
3.	WELL TYPE <i>oil</i>	WELL CATEGORY <i>Abandoned</i>	JOB PURPOSE <i>P.T.A</i>	WELL PERMIT NO.		WELL LOCATION	
4. REFERRAL LOCATION	INVOICE INSTRUCTIONS						

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575					MILEAGE	50		mi		2.50	125.00
576					Pump charge	1		EA			500.00
330					5m O Cement	270		SKS		9.50	2565.00
275					Hulls	9		SKS		22.00	198.00
581					Bulk Service charge	300					300.00
583					Drayage	745	75		T.M.	75	559.31

RECEIVED
 JAN 06 2003
 KCC WICHITA

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X
 DATE SIGNED: *12-10-02* TIME SIGNED: *1200*
 A.M.
 P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	<i>4247</i>	<i>31</i>
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?						
WE UNDERSTOOD AND MET YOUR NEEDS?						
OUR SERVICE WAS PERFORMED WITHOUT DELAY?						
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	<i>225</i>	<i>!!</i>
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	<i>4472</i>	<i>42</i>
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND						

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR: *Lemy* APPROVAL: *R. Hochman*

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 12-10-07 PAGE NO. 1

CUSTOMER *Murphy Dng. Co.* WELL NO. *A-6* LEASE *Nichol* JOB TYPE *P.T.A.* TICKET NO. *5113*

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1200							on loc TD 3535 open hole 3534-35
								Tbg at 3530
	1220							Pump 100 SKS 5M0 CMT + 400 hulls
	1235							Pull Tbg To 1760+-
								Pump 90 SKS CMT + 200 hulls
								Pull Tbg out of hole
								hookup to 5 1/2 + Pump 40 SKS CMT
								Reset to 200 w/ 100. Hulls 200
								ST CIRC oil out 8 5/8
								open 8 5/8 + Pump 10 BBC CMT + 200
								100 # hulls CMT to Pit out 8 5/8
								Close 8 5/8 + Pump 20 SKS CMT 100 hull
								PSF 5 1/2 + 8 5/8 To 400
								shut in at 300
	1530							Job complete
								Total 270 SKS CMT
								900 # hulls

RECEIVED
JAN 06 2008
KCC WICHITA