

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

15-147-00608-00-00

WELL PLUGGING APPLICATION FORM
(File One Copy)

API Number 10-30-50 (of this well). (This must be listed; if no API# was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447 6-92

ADDRESS 110 S. Main #800, Wichita, KS 67202 PHONE # (316) 265-5624
1650' FSL

LEASE/FARM Ray "A" WELL NO. 6 WELL LOCATION 2310' FEL COUNTY Phillips

SEC. 32 TWP. 5S RGE. 20 (E) or Total Depth 3538' PLUG BACK TD _____

CHECK ONE:

OIL WELL GAS WELL _____ D & A _____ SWD OR INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 204' CEMENTED WITH _____ 150 SACKS

CASING SIZE 5-1/2" SET AT 3529' CEMENTED WITH _____ 150 SACKS

PERFORATED AT 3318, 3338, 3340, 3352, 3354, 3440, 3442, 3464, and OH 3529-38'

CONDITION OF WELL: GOOD _____ POOR CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING RIH and perf w/ 4 SPF at 1645' and 1000'. Run 2-3/8" workstring to 3500' and spot 65/35 cmt w/ 8% gel to surface. Attempt to circulate cmt between the 8-5/8" and 5-1/2" casings. If needed, tie onto the 8-5/8" and fill to surface w/ cmt.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: _____ 3-15-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J. D. Hininger PHONE # (913) 434-7681
ADDRESS Drawer D, Plainville, KS, 67663

PLUGGING CONTRACTOR J.W. Gibson Well Service Co. LICENSE NO. 5866 842
ADDRESS 505 W. Commercial, Logan, KS, 67646 PHONE # (913) 689-7573

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

RECEIVED
STATE CORPORATION COMMISSION

MAR - 4 1992

SIGNED: Carla J. Davis
Carla J. Davis
(Operator or Agent)

CONSERVATION DIVISION
Wichita, Kansas

DATE: 3-2-92

4

3-4-92

WELL RECORD

15-147-00608-00-00

Company Cities Service Oil Co. Well No. 6 Farm Ray "A"
 Location 990' South and 330' East of Center Sec. 32 T. 5 R. 20W
 Elevation 2136 (2133 Gr.) County Phillips State Kansas
 Drlg. Comm. October 15, 1950 Contractor R. W. Rine Drilling Company
 Drlg. Comp. October 30, 1950 Acid None
 T. D. 3534' Initial Prod. Physical Potential: 177 oil, 32% water, 24 hrs. (11-2-50)

CASING RECORD:

8-5/8" @ 204' cem. 150 sx cement & 200# C.C.
 5-1/2" @ 3529' cem. 150 sx cement

Corr. Lansing 3282'
 Corr. Arbuckle 3526'
 Reagan 3531'
 Penetration 3'
 Total Depth 3534'

FORMATION RECORD:

clay, sand, shale 0-205
 shale 595
 sand, shale, shells 975
 sand 1425
 shale 1475
 shale & shells 1650
 anhydrite 1690
 red bed & shale 1890
 shale & shells 2300
 lime shells & shale 2540
 lime & shale 2775
 shale 2845
 shale & lime 2960
 lime & shale 3145
 lime 3528
 sand 3533
 sand 3533 RTD = 3531 SLM
 sand 3534 T. D.

Phillips:

3/4" bailer oil in 30 mins. at 3531
 500' oil in 2 hrs. at 3534
 1380' oil in 3-1/4 hrs.
 2060' oil in 6-1/4 hrs.

SYFO: 500' 1°
 1000' 1°
 1500' 1°
 2000' 1°
 2500' 1°
 3000' 0°

7-7/8" rotary hole.

RECEIVED
 STATE CORPORATION COMMISSION

MAR - 4 1992

CONSERVATION DIVISION
 Wichita, Kansas

15-147-00608-00-00



Kansas Corporation Commission

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

March 5, 1992

OXY USA INC
110 S Main 800
Wichita KS 67202

Ray A 6
1650'FSL-2310'FEL
Sec. 32-05-20W
Phillips County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000: If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200

Conservation Division
William R. Bryson
Director

200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238