

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 DERBY BLDG,
WICHITA, KANSAS 67202

Rev. 12-11-80
FORM CP-1

WELL PLUGGING APPLICATION FORM
FILE ONE COPY

15-147 20,352-00-00

API NUMBER 15-147-22,352-0000 (OF THIS WELL)
(THIS MUST BE LISTED, IF NO API# AVAILABLE PLEASE NOTE DRILLING COMPLETION DATE.)

LEASE OWNER F & M Oil Co., Inc.

ADDRESS 422 Union Center, Wichita, KS 67202

LEASE (FARM NAME) McLaughlin WELL NO. 1

WELL LOCATION C SW NE SEC. 34 TWP. 5S RGE. 18W (EAST) (WEST)

COUNTY Phillips TOTAL DEPTH 3606' FIELD NAME _____

OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A XX

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? YES
(IF NOT STATE REASON WHY)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12:30 p.m., 9/23/81

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wilmer Dreiling (Toolpusher) ADDRESS 408 Jefferson, Ellis, KS 67637

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. _____

ADDRESS 801 Union Center, Wichita, KS 67202

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME F & M Oil Co., Inc.

ADDRESS 422 Union Center, Wichita, KS 67202

AND PAYMENT WILL BE GUARANTEED BY APPLICANT OF ACTING AGENT.

Rec'd
10-28-81

SIGNED: Jack L. Partridge
APPLICANT OR ACTING AGENT
Jack L. Partridge, Vice Pres.
DATE: September 25, 1981

CONTRACTORS WELL LOG

OPERATOR: F & M Oil Co., Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: McLAUGHLIN #1
 LOCATION: C SW NE, Sec. 34-5S-18W,
 Phillips County, Kansas
 SPUD DATE: 9/18/81
 COMPLETION DATE: 9/23/81

0	254	Sand & Shale
254	940	Shale
940	1140	Sand
1140	1440	Shale
1440	1470	Anhydrite
1470	3080	Shale
3080	3232	Shale & Lime
3232	3350	Lime
3350	3606	Lime & Shale
	3606	Rotary Total Depth

Spud hole @ 4:15 p.m., 9/18/81. Drilled 248' of a 12 1/4" hole. Ran 6 jts. of 8 5/8" 20# casing set @ 248' and cemented with 175 sx. Common 2% gel, 3% c.c. Plug was down @ 9:45 p.m., 9/18/81.

3606' RTD. Set 1st plug @ 750' with 60 sx. Set 2nd plug @ 220' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole. 50-50 posmix, 6% gel. Job complete @ 12:30 p.m., 9/23/81.

SAMPLE TOPS:

Anhydrite 1430'
 B/Anhydrite 1470'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the McLAUGHLIN #1, C SW NE, Sec. 34-5S-18W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 5th day of October, 1981.

Elizabeth G. Terry
 Elizabeth G. Terry
 NOTARY PUBLIC

my commission expires 7-13-85

RECEIVED
 STATE CORPORATION COMMISSION

OCT 8 1981
 CONSERVATION DIVISION
 Wichita, Kansas



STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

INVOICE and WELL PLUGGING AUTHORITY

October 29, 1981

INVOICE NUMBER: 8106-W

(1)

TO: F & M. Oil Company
422 Union Ctr. Bldg.
Wichita, KS. 67202

15-147-20352-00-00

PLUGGING ASSESSMENT AS FOLLOWS: PAYABLE UPON RECEIPT

McLaughlin #1
C SW NE, Sec. 34-5S-18W
Phillips
T.D. 3606' \$117.20

NOTE: We also need the following before our file is completed:


- _____ Well Plugging Record (CP-4)
- _____ Well Log
- _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



For Administrator

Mr. Gil Balthazor, Box 9, Palco, KS., 67657
is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE