

11-13 4-041847 13-147-00535-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 11-09-48

NE NW NE /4 SEC. 32, 05 S, 20 W  
4950 feet from S section line  
1650 feet from E section line

Operator license# 5447  
Operator: OXY USA, Inc.  
Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Lease: Ray C Well # 3  
County: Phillips 117.00  
Well total depth 3600 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 203 feet  
w/250 sxs.cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Halliburton Cementing, Inc. License# \_\_\_\_\_

Address: Hays, Kansas 67601

Company to plug at: Hour: 1:00 P.M. Day: 13 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3586' w/150 sxs.  
Open hole.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 2:00 P.M., Day: 13, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1125' and 1770' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3600'. Pumped 65 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 jts. to 2100'. Pumped 65 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 35 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 25 sxs cement. Max. P.S.I. 500#. Closed in 5 1/2" at 175# pressure. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 200#. S.I.P. 125#. Total 240 sxs cement used.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING , CASING \_\_\_\_\_ Elevation: 2204 G.L.

I did [ ] observe the plugging.

Dennis L. Hamel  
(agent)

DATE ~~JAN 13 1997~~  
INV. NO. 47338