

4-041610

8-30 15-147-00534-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 12-10-41

SW NW NE /4 SEC. 32, 05 S, 20 W  
990 feet from W section line  
2310 feet from E section line

Operator license# 5447

Lease Ray 'C' well # 2

Operator: OXY USA, Inc.

County Phillips

Address: 110 S. Main  
Suite #800  
Wichita, Kansas 67202

Well total depth 3566 feet <sup>115.90</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 149 feet  
w/125 sxs.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton Cementing License#    

Address: Oberlin, Kansas

Company to plug at: Hour: 8:00A.M. Day: 30 Month: August Year: 94

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone:    

Were: 5 1/2" casing set @ 3552' w/100 sxs. cmt. O.H. @ 3552' - 3566'.  
Anhy. @ 1700' - Dakota @ 1060'.  
Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 6:00P.M., Day: 30, Month: August, Year: 94

Actual plugging report: R.I.H. with tubing to 3100'. Spotted 60 sxs.  
cement with 200# hulls. Pulled to 3100' - spotted 60 sxs. cement with  
100# hulls. Pulled to 1100' - spotted 75 sxs. cement with 100# hulls.  
Cement circulated at surface. Pulled tubing and squeezed casing with  
55 sxs. cement. Max. 450#. Shut in at 150#. Hooked-up to 8 5/8" S.P.  
Squeezed 50 sxs. cement with 100# hulls. Max. 100# P.S.I. Shut in 100#.

Remarks: Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO  
Bottom plug(in place):YES X ,CALC Dakota plug:YES X ,NO  
Plugged through TUBING X , CASING . Elevation:    

I did     ] observe the plugging.

Dennis L. Hamel  
(agent) 9-14-94

**INVOICED**  
DATE 9-26-94  
INV. NO. 41260

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 14 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS