

10-15-87 15-147-00533-00-00

6 030990

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1957
NE NE NE, SEC. 32, T 5, S, R 20 W/E
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Ray C Well # 1

Operator: Cities Service Oil and Gas
Name & Address 3545 N. W. 58th Street
Oklahoma City, Ok. 73112

County Phillips Co. 116.42
Well Total Depth 3582 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 172

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number
Address Hays, Kansas

Company to plug at: Hour: PM Day: 15 Month: Oct. Year: 19 87

Plugging proposal received from J. D. Hininger
(company name) Cities Service (phone)

were: 8 5/8" set at 172' w/125 sks 5 1/2" set at 3592' w/100 sks. Open hole.
Perf 5 1/2" at 1725' w/4 shots at 1110' w/3 shots at 170' w/3 shots. Ordered
200 sks Econolite Cement Blend 65/35 Pozmix 10% Gel 2% Dical 4 sks Hulls.
Halliburton Cement Co. OWS Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:00PM Day: 15 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Squeeze 5 1/2" casing w/150 sks cement blend w/4 sks Hulls.

Max PSI 300# Close in PSI 150#. Squeeze 8 5/8" - 5 1/2" Annulus w/195 sks Cement
Blend 4 sks Hulls. Max Psi 300#. Close in PSI 150#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION
12-7-87
DEC 7 1987

DATE 12-8-87

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 19198

Carl Goodrow

10-15 JAN 14 1988