

11-13 4-041849

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147-20,522 -00-01

SE NW NE /4 SEC. 32, 05 S, 20 W
4290 feet from S section line
1650 feet from E section line

Operator license# 5447

Lease: Ray C Well # 5

Operator: OXY USA, Inc.

County: Phillips 118.85

Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Well total depth 3657 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 358 feet
w/250 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 10:00 A.M. Day: 13 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3653' w/175 sxs.
Open hole. D.V. at 1740' w/400 sxs.
Perfs 3595' - 3597'. PBT 3633'.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 11:45 A.M. Day: 13, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Well was D.V. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3610'. Pumped 65 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 jts. to 2100'. Pumped 65 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 35 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 20 sxs cement. Max. P.S.I. 500#. S.I.P. 400#. Hooked up to 8 5/8" casing and pumped 5 sxs MIDCON 2 cement with 2% CC. Max. P.S.I. 1000#. S.I.P. 900#. Total 190 sxs cement used.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING. Elevation: 2206 G.L.
Anhy.plug: YES X NO
Dakota plug: YES X, NO

I did [X] / did not [] observe the plugging.

INVOICED

DATE JAN 13 1997

INV. NO. 47336

Dennis L. Hamel (agent)

Form CP-2/3

1-10-97