

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00615-00-00
Spot: CNESENW Sec/Twnshp/Rge: 32-5S-20W
3690 feet from S Section Line, 3030 feet from E Section Line
Lease/Unit Name: RAY B Well Number: 2
County: PHILLIPS Total Vertical Depth: 3585 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet: \$116.51
Surface Casing: Size 8.625 feet: 165 125 SX CMT
Production: Size 5.5 feet: 3563 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/11/2002 11:30 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: RIC HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 350 sxs cement and 800# hulls.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/11/2002 2:00 PM

KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 165' w/125 sxs cement. 5 1/2" casing at 3563' w/100 sxs cement.
Ran tubing to 3548' - spotted 100 sxs cement and 400# hulls.
Pulled tubing to 1780' - circulated with 100 sxs cement and 300# hulls.
Pulled all tubing and squeezed with 15 sxs cement.
Max. P.S.I. 400#. S.I.P. 400#.
Tied to 8 5/8" x 5 1/2" annulus - squeezed 75 sxs cement and 100# hulls.
Max. P.S.I. 250#. S.I.P. 200#.
Total of 290 sxs 60/40 pozmix - 10% gel and 800# hulls.

RECEIVED
JAN 03 2003
KCC WICHITA

Remarks: SWIFT SERVICES CEMENT - TRACY TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger L Moses
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 1-3-03

INV. NO. 200.3061024

DEC 30 2002