

4-010777

4-22  
15-147-00608-0000

2010  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- -

SW NW SE /4 SEC. 32, 05 S, 20 W  
1650 feet from S section line  
2310 feet from E section line

Operator license# 5447

Lease Ray well # A-6

Operator: OXY USA, Inc.

County Phillips

Address: Box 26100  
Oklahoma City, OK 73126

Well total depth 3534 feet <sup>114.85</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 204 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: OXY USA, Inc. License# 5447

Address: Box 26100, Oklahoma City, OK 73126

Company to plug at: Hour: 9:00A.M. Day: 22 Month: April Year: 92

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: \_\_\_\_\_

Were: Perf Dakota @ 1000' - Anhydrite @ 1645'.  
Order 400 sx. cement 65/35 pozmix - 8% gel. - 100# flocele - 500# hulls.  
Run work string tubing to 3510'. Dakota top 733'. K.C. perf. - 3318' -  
3464'- Reagan sand top 3529' - 5 1/2" casing @ 3534' - Elv. 2133'.

Plugging Proposal Received by: Dale F. Balthazor

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:45P.M., Day: 22, Month: April, Year: 92

Actual plugging report: Pump down tubing - 50 sx. cement - then 50 sx.  
cement w/100# hulls. Pull tubing to 2500' - pump down tubing 100 sx.  
cement w/150# hulls. Pull tubing to 1200' - pump down tubing 75 sx.  
cement w/100# hulls. Cement circulated - pumped down 8 5/8" 100 sx.  
cement w/150# hulls. Max. pressure 500#. Holding 300#. Pumped down  
casing 25 sx. cement. Max. pressure 700#. Holding 400#.

Remarks: Halliburton Cement Company - Work pit lined.

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2133 GL

I did  / did not  observe the plugging.

DATE 5-5-92

INV. NO. 35135

4-22 MAY 19 1992

*Dale F. Balthazor*  
(agent)

RECEIVED  
APR 27 1992  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
4-27-92