

11-13 4-041848 15-147-00536-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 11-22-48

SW NE NE /4 SEC. 32, 05 S, 20 W  
4290 feet from S section line  
990 feet from E section line

Operator license# 5447

Lease: Ray C Well # 4

Operator: OXY USA, Inc.

County: Phillips 116.48

Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Well total depth 3584 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 205 feet  
w/250 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 8:00 A.M. Day: 13 Month: November Year: 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3581' w/150 sxs.  
Open hole.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 9:15 A.M., Day: 13, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1130' and 1760' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3600'. Pumped 65 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 jts. to 2100'. Pumped 65 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 30 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 20 sxs cement. Max. P.S.I. 400#. S.I.P. 300#. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 400#. S.I.P. 300#. Total 230 sxs cement used.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING X, CASING. Elevation: 2183 G.L.  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO

I did not observe the plugging.

Dennis L. Hamel (agent)

INVOICED  
DATE JAN 13 1997  
INV. NO. 47337