

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-00078-00-00  
Spot: NENE Sec/Twnshp/Rge: 7-22S-22W  
660 feet from N Section Line, 660 feet from E Section Line  
Lease Name: GUS MILLER A Well #: 9  
County: HODGEMAN Total Vertical Depth: 4624 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

PROD Size: 5.5 feet: 4598 WITH 100 SX CMT  
SURF Size: 8.625 feet: 258 WITH 200 SX CMT

*#150<sup>28</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/22/2004 11:35 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO INC. Phone: (316) 772-1155

Proposed Plugging Method: PLUG AT 4100' WITH 200# HULLS & 25 SX CMT. PLUG AT 2800' WITH 25 SX CMT & HULLS. PLUG AT 1890' WITH 50 SX CMT. TEST CASING. PERFORATE @ 600'. PUMP 80 SX CMT + CASING VOLUME ABOVE PERFS. PUMP 100 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/23/2004 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 4100' WITH 25 SX CMT & 100# HULLS WITH TUBING. 2ND PLUG PULL TUBING TO 2800'. PUMP 25 SX CMT & 100# HULLS. 3RD PLUG PULL TUBING TO 1890' & CEMENT WITH 50 SX CMT W/2% CC. PULLED TUBING. SDON.  
11/23/04: PUMPED 8 BBL WATER & CASING PRESSURED TO 600# & HELD FOR 15 MINUTES. PERFORATED @ 600' & PUMPED 130 SX CMT. MAXIMUM PRESSURE 1200#. SHUT IN PRESSURE 300#. TIED ONTO BACKSIDE & PUMPED 30 SX CMT. PRESSURED TO 300# & HELD.

Perfs:


Top	Bot	Thru	Comments
4522	4530		
4456	4459		
4297	4302		
4123	4126		

RECEIVED  
DEC 01 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL & 4% CC BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed Michael Maier  
(TECHNICIAN)

INVOICED  
DATE 12-1-04  
INV. NO. 2005060866

*[Signature]*