

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-10008-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 3-24S-24W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: SCHRAEDER Well #: 3
County: HODGEMAN Total Vertical Depth: 4706 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

PROD Size: 5.5 feet: 4685 WITH 250 SX CMT
SURF Size: 8.625 feet: 377 WITH 250 SX CMT

95
#152

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2004 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: WAYNE GERSTNER Company: BEREXCO Phone: (316) 772-1155

Proposed Plugging Method: SET CIBP @ 4500' & 2 SX CMT. PLUG AT 1580' WITH 15 SX GEL & 50 SX CMT. PLUG AT 800' WITH 80 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2004 11:58 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 4706'. 1ST PLUG AT 4476' WITH 200# HULLS & 25 SX CMT. 2ND PLUG PULL 2 7/8" TUBING TO 2806'. PUMP 40 SX CMT & 100# HULLS MIXED IN CMT. 3RD PLUG PULL TUBING TO 1580' & PUMP 50 SX CMT. PULL TUBING OUT OF HOLE. SDON TAG TOC @ 804'. 4TH PERFORATE 5 1/2" @ 804'. SET CMT RETAINER AT 700'. RUN 2 7/8" TUBING & STINGER. ESTABLISH RATE AND PUMP 100 SX CMT. MAXIMUM PRESSURE 200#. 5TH PULL OUT OF RETAINER AND CIRCULATE 5 1/2" TO SURFACE WITH 65 SX CMT. 6TH PLUG PUMP 5 SX CMT DOWN ANNULUS. PRESSURE TO 400#.

Perfs:


Top	Bot	Thru	Comments
4685	4706	OH	

RECEIVED
DEC 01 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Steve Durrant

(TECHNICIAN)

INVOICED

DATE

12-1-04

INV. NO.

2005060866