

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-20646-00-00
Spot: SENWSENW Sec/Twnshp/Rge: 9-30S-37W
3450 feet from S Section Line, 3500 feet from E Section Line
Lease Name: TUTTLE Well #: 3-9
County: GRANT Total Vertical Depth: 2950 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

CIBP Size: feet: 2370 WITH 2 SX CMT
PROD Size: 5.5 feet: 2950 WITH 410 SX CMT
SURF Size: 8.625 feet: 620 WITH 275 SX CMT

88
495

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/11/2004 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2370' WITH 2 SX CMT. PLUG AT 640' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: NONE
Date/Time Plugging Completed: 11/11/2004 5:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 2859'. SET CIBP @ 2370' WITH 2 SX CMT ON TOP WITH BAILER. 1ST PLUG LOAD HOLE & PUMP 50 SX CMT AT 525'. 2ND PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2428	2740		

RECEIVED
DEC 01 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 525' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

[Signature]

(TECHNICIAN)

INVOICED

DATE: 12-1-04
WELL NO: 2005060870

Form CP 2/3
[Signature]