

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22652-00-00  
Spot: NESWSE Sec/Twnshp/Rge: 5-19S-21W  
990 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: FOOS Well #: 1  
County: NESS Total Vertical Depth: 4250 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

MSCC Size: feet: 1377 CMT TO SURFACE  
PROD Size: 5.5 feet: 4245 WITH 375 SX CMT  
SURF Size: 8.625 feet: 369 WITH 210 SX CMT

13  
#138

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/16/2004 3:20 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Revd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: PUMP 25 SX CMT & 300# HULLS. PUMP 20 SX CMT & 120 SX CMT. PRESSURE TEST. PUMP 15 SX CMT DOWN BACKSIDE & PRESSURE TEST.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/16/2004 4:10 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

DV TOOL @ 1377' CMT TO SURFACE. PUMPED 25 SX CMT & 300# HULLS FOR BOTTOM PLUG. PUMP 20 SX GEL - 60 BBL WATER - 120 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 500#. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD. TOPPED OFF WITH 20 SX CMT ON 11/17/04.

Perfs:


Top	Bot	Thru	Comments
4245	4250	OH	

RECEIVED  
DEC 01 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed Michael J Maier  
(TECHNICIAN)

INVOICED  
DATE 12-1-04  
2005060864

Form SF-2/3