

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-00357-00-00
Spot: NWSW Sec/Twnshp/Rge: 6-21S-6W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: HUGHES Well #: 1
County: RICE Total Vertical Depth: 3490 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3471 75 SX CMT
SURF Size: 8.625 feet: 154

#113 43

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2004 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Sand to 3420' & 5 sxs; 1050' & 35 sxs; 600' & 35 sxs; and 300' to 0'.
Plugging Method:

Plugging Proposal Received By: JACK LUTHI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2004 3:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3420' and 5 sacks of common cement. Cut 5-1/2" casing at 2420'. Pulled to 1050' and pumped 35 sacks of cement. Pulled to 600' and pumped 35 sacks of cement. Pulled to 300' and circulated cement to surface.

Copeland #24284

60/40 posmix with 4% gel.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 01 2004
CONSERVATION DIVISION
WICHITA, KS

Perfs:

Top	Bot	Thru	Comments
19			OH
RECEIVED KCC DISTRICT #2 NOV 23 2004 WICHITA, KS			

Remarks:

Plugged through: CSG

District: 02

Signed Jack L Luthi
(TECHNICIAN)

INVOICED

DATE 12-1-04
NO. 2005060865