

4-041988

9-24

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147-00,540 00-00

NE NW SW /4 SEC. 33, 05 S, 20 W
2310 feet from S section line
4290 feet from E section line

Operator license# 30606

Lease: Nichol Well # 2

Operator: Murfin Drilling Company

County: Phillips 116.42

Address: 250 N. Water
Wichita, Kansas 67202

Well total depth 3582 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 171 Feet
W/125 sxs cmt.

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License# -

Address: Pratt, Kansas 67124

Company to plug at: Hour: 8:00 A.M. Day: 24 Month: September Year 1998

Plugging proposal received from: Jim Nowell

Company: Murfin Drilling Company Phone: -

Were: 5 1/2" casing set at 3571' w/100 sxs cement. Perfs at 3571' - 3579'.
Ordered 250 sxs Mid-Con II plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:00 P.M., Day 24, Month: September, Year: 1998

Actual plugging report: Perforated casing at 1176' and 1699'. MIRU Howco and pumped 80 sxs of Mid-Con II with 300# hulls thru tubing at 3550'. Pulled tubing to 1700' and pumped 80 sxs Mid-Con II with 200# hulls to circulate at surface. Hooked-up to 5 1/2" casing and squeezed with 15 additional sxs. S.I.P. 200#. 8 5/8" S.P. Squeezed 40 sxs Mid-Con II. S.I.P. 150#.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING CASING Elevation: G.L.

I did / did not observe the plugging.

Dennis J. Hamel
(agent)

Form CP-2/3

10-19-98

60122

PHILLIPS COUNTY RECORDS
1998 SEP 24 11:00 AM

10-19-98

10