

4-041472

6-2

15-147-00538-00-00

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 1-9-48

N2 NW NE /4 SEC. 33, 05 S, 20 W
4950 feet from S section line
1980 feet from E section line

Operator license# 5447Lease Kohman "A" well # 3Operator: OXY USA, Inc.County Phillips

Address: 110 S. Main
Suite #800
Wichita, Kansas 67202

Well total depth 3548 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 195 feet

Aband. oil well X, Gas well , Input well , SWD , D & A Plugging contractor: Halliburton Cementing License# -Address: Oberlin, KansasCompany to plug at: Hour: 9:00A.M. Day: 2 Month: June Year: 93Plugging proposal received from: Dave JubyCompany: OXY USA, Inc.Phone:

Were: 5 1/2" casing set @ 3531' w/150 sx. cement. Perf. @ 3272' - 3548'.
Anhy. 1755' - Dakota @ 1085'. Plug back @ 3450'.
Ordered 225 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.
Plus 9 sx. gel.

Plugging Proposal Received by: Dennis L. HamelPlugging operations attended by agent? All[X], Part[], None[]Completed: Hour: 1:30P.M., Day: 2, Month: June, Year: 93

Actual plugging report: R.I.H. with tubing to 3260'. Spotted 25 sx.
cement with 100# hulls. 9 sx. gel. spacer. Pulled tubing to 1772'.
Spotted 100 sx. cement with 200# hulls to circulate at surface.
P.O.O.H. with tubing squeezed 50 sx. cement with 100# hulls down casing.
Max. 300# P.S.I. Hooked-up to 8 5/8" and pumped 50 sx. cement with
100# hulls. Max. 100#.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did[X] / did not[] observe the plugging.**INVOICED**DATE JUL 13 1993INV. NO. 38095

(agent)

JUN 30 1993

Form CP-2/3

6-30-93
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION