

11-12 4-041852

15-147-00542-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 08-09-42  
60'E.of C.of  
SW NE SW /4 SEC. 33 , 05 S, 20 W  
1650 1692 feet from S section line  
3570 3588 feet from E section line

Operator license# 5447

Lease: Nichol Well # 4

Operator: OXY USA, Inc.

County: Phillips 117.65

Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Well total depth 3620 feet  
Conductor Pipe: 0 inch @ 30 feet  
Surface pipe 10 3/4 Inch @ 152 feet  
w/125' sxs.cmt.

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Halliburton Cementing, Inc. License# \_\_\_\_\_

Address: Hays, Kansas 67601

Company to plug at: Hour: 1:00 P.M. Day: 12 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 7" casing set at 3620' w/100 sxs.  
Open hole. Perfs at 3551' - 3554'.  
PBTD 3586'.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 3:00 P.M., Day: 12, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 7" to 10 3/4" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1150' and 1700' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3600'. Pumped 105 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 jts. to 2100'. Pumped 105 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 45 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 7" casing and pumped 15 sxs cement. Max. P.S.I. 500#. S.I.P. 500#. Hooked up to 10 3/4" casing and pumped 65 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 300#. S.I.P. 150#. Total 355 sxs cement used.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_  
Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING X, CASING \_\_\_\_\_ Elevation: 2128 G.L.

I did not observe the plugging.

**INVOICED**

DATE JAN 13 1997

INV. NO. 47331

Dennis L. Hamel  
(agent)