

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21774-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 36-15S-12W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: KAUFMAN E Well #: 1
County: RUSSELL Total Vertical Depth: 3327 feet

Operator License No.: 6357
Op Name: WEBCO OIL CO., INC.
Address: 2136 NE 90 AVE.
HOISINGTON, KS 67544

CIBP Size: feet: 3310
PROD Size: 5.5 feet: 3317 100 SX CMT
SURF Size: 8.625 feet: 342 190 SX CMT

108¹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/23/2004 12:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRIAN SCHUMACHER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/23/2004 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Sanded off bottom to 2800'.
Topped with 5 sxs cement using a dump bailer.
Pulled into casing - parted at 580'.
Tied onto casing and pumped 175 sxs 60/40 pozmix with 400# hulls mixed in.
Pulled casing to 40' and pumped 45 sxs cement.
POOH. Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3208	3216		
3172	3174		
3062	3066		
3034	3039		
2946	2952		
2872	2878		

RECEIVED
DEC 01 2004
KCC WICHITA

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #25796.

Plugged through: CSG

District: 04

Signed: 
(TECHNICIAN)

NOV 24 2004

INVOICED
DATE 12-1-04
INV. NO. 2005060871

INDEXED

INDEPENDENT OIL & GAS SERVICES CORP
 575 4TH FINANCIAL CENTER #1 E. KAUFMAN 36-15-12W
 WICHITA, KS 67202 NW SW SW
 CONTR DUKE DRILLING CO INC CTY RUSSELL
 GEOL CHARLEY SHANK FIELD KRAFT-PRUSA
 E 1855 KB CM 9/7/81 CARD ISSUED 11/12/81 P 60 BOPD
 ARB OH 3317-3327
 API 15-167-21,774

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		754	+1101
TOP		2644	-789
HEEB		2927	-1072
TCR		2946	-1091
BR LM		3018	-1163
LANS		3033	-1178
B KC		3288	-1433
CONG		3308	-1453
ARB		3317	-1462
RTD		3326	-1471
LTD		3327	-1472

8-5/8" 342/190sx, 5 1/2" 3317/100sx
 DST (1) 2871-2904/30-30-30-30, REC
 15' WCM, SIP 521-336#, FP 31-33/
 35-35#, HP 1584-1562#
 DST (2) 2923-2960/30-30-30-30, REC 20'
 O SPKD M, SIP 33-31#, FP 29-29/
 29-29#, HP 1573-1551#, BHT 102°
 DST (3) 3031-3045/30-30-60-60, GTS 75",
 GA 4 MCFG, REC 100' O&GCWM, SIP
 500-618#, FP 29-29/31-31#, HP 1691-
 1631#, BHT 104°

(OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS