

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00543-00-00

Spot: SWSWSW

Sec/Twnshp/Rge: 33-5S-20W

⁴⁴⁰~~230~~ feet from S Section Line, 4950 feet from E Section Line

Lease/Unit Name: NICHOL A

Well Number: 6

County: PHILLIPS

Total Vertical Depth: 3535 feet

Operator License No.: 30606

Conductor Pipe: Size

feet:

8114.89

Op Name: MURFIN DRILLING CO., INC.

Surface Casing: Size 8.625

feet: 195

250 SX CMT

Address: 250 N. WATER, STE 300

Production: Size 5.5

feet: 3533

150 SX CMT

WICHITA, KS 67202

Liner: Size

feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/10/2002 12:30 PM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: RIC HOCKMAN

Company: MURFIN DRILLING CO., INC.

Phone: (785) 421-2701

Proposed
Plugging
Method:

Ordered 300 sxs of Mid-Con II cement and 900# hulls.
Plug thru tubing.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/10/2002 3:00 PM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" Surface casing set at 195' w/250 sxs cement.
5 1/2" Production casing set at 3533' w/150 sxs cement.
Perforated 5 1/2" casing at 1675' and 1000'.
Ran tubing to 3530' - pumped 100 sxs cement with 400# hulls.
Pulled tubing to 1750' - pumped 90 sxs cement with 200# hulls.
Circulated cement to surface.
Pulled tubing surface.
Topped 5 1/2" production casing with 40 sxs cement and 300# hulls.
Cement circulated from 8 5/8" surface casing. Circulated cement.
Connected to 5 1/2" casing - pumped 40 sxs cement.
S.I.P. 300#.
Connected to 8 5/8" surface casing.
Pumped 1 bbl water. S.I.P. 300#.
Plug complete.

RECEIVED
DEC 18 2002
KCC WICHITA

Remarks: SWIFT CEMENT COMPANY.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED

DATE

12-19-02

INV. NO.

2003060953

Form CP-2/3

DEC 11 2002

CITIES SERVICE OIL CO

#6

NICHOL

33-5-20W
APP SW SW SW

Contr.

PHILLIPS

County

E 2140

Comm.

Comp.

12-21-51

IP

123 BOPD

PHY POT

Tops	Depth	Datum
HEEB	3247	-1107
DODGE	3268	-1128
LANS	3287	-1147
B/KC	3484	-1344
REAG	3534	-1394
T.D.	3535	-1395

Casing

5" 3533

2560' OIH/11 HRS
PMP 61 BQ/10 HRS

RAY POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

PHILLIPS