

NOV 30 2004

CONSERVATION DIVISION  
WICHITA, KS

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 081-20379 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; If no API # was issued,

Indicate original spud or completion date 09/17/85

Well Operator: WESTPORT OIL & GAS COMPANY, LP KCC License #: 33002  
(Owner/Company Name) (Operator's)

Address: 5735 PINELAND, SUITE 300 City: DALLAS

State: TEXAS Zip Code: 75231 Contact Phone: (214) 692-1800

Lease: WAYNE LUCAS WAYNE <sup>REVOOPER</sup> KCC Well #: 4 Sec. 21 Twp. 28 S. R. 34  East  West

C NW NE Spot Location / OOOO County: HASKELL

4620 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 9-5/8" Set at: 1897' Cemented with: 710 Sacks

Production Casing Size: 5-1/2" Set at: 5633' Cemented with: 635 Sacks

List (ALL) Perforations and Bridgeplug Sets: 5326'-34' - CIBP@5250' W/2SXS; 4863'-??' - CIBP@4800'W/2SXS; 4722'-??' - CIBP @ 4690'  
W/2SXS; 4618'-4622' - CIBP@4575'W/2SXS; 4375'-4387' - OPEN

Elevation: 3032' ( B.G.L. /  K.B.) T.D.: 5634' PBTD: 4560' Anhydrite Depth: N/A  
(Steno Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk In Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): SET CIBP@4300'W/2 SXS.CMT.; CIRC.WELL W/PXA MUD;  
CUT&PULL 5-1/2" CSG.@1950'; PUMP 60 SX.CMT.PLUG@1950'-1845' - WOC & TAG; PUMP 50 SX.CMT.PLUG@750'-  
650'; SPOT 5 SX.CMT.SURF.PLUG@ 13'-3'; DIG OUT & CUT OFF WELLHEAD 3' B.G.L.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? 2-7/8" TBG. @ 4,447' - TAC @ 4297'  
EST. (172) RODS.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: DAVID A. EYLER

Phone: (432) 687-3033

Address: 223 W. WALL AVE., SUITE 707 City / State: MIDLAND, TEXAS 79701

Plugging Contractor: SARGENT & HORTON PLUGGING, INC. KCC License #: 31151  
(Company Name) (Contractor's)

Address: RR1, BOX 49BA, TYRONE, OK 73951 Phone: (580) 854.6515

Proposed Date and Hour of Plugging (if known?): ESTIMATED 12/01/04

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/10/04 Authorized Operator / Agent: David A. Eyer  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

3/05

1/05



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Westport Oil and Gas Company LP  
5735 Pineland, Suite 300  
Dallas, TX 75231

November 30, 2004

Re: LUCAS WAYNE #4  
API 15-081-20379-00-00  
NWN 21-28S-34W, 4620 FSL 1980 FEL  
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely



David P. Williams  
Production Supervisor